



Northeast Wisconsin Technical College - Shawano Campus

Owner: Northeast Wisconsin Technical College
Shawano, Wisconsin

Project Type: New Campus Facility

Project Cost: \$965,000

About the Project: Construction of a one story building, steel framed structure with a brick and backup CMU exterior designed to accommodate a future second story. This building was set into the slope of the hillside requiring foundation walls to extend 36" above the first floor elevations.

The sandy soil materials found in this area were suitable for backfilling the foundations, reducing the cost of the project. The NWTC – Shawano campus was built with state of the art high tech classrooms, laboratories, offices, toilet room facilities, a spacious lounge and reception area to accommodate faculty, students, and staff.

Basic Construction:

Building size - 12,000 sq. ft.

Footing & Foundation walls – concrete

Floors – concrete slab on grade

Exterior walls – brick and split stone w/masonry backup block

Roof – metal deck with sheet membrane

Entrances & Windows - aluminum

Floor Covering – ceramic, porcelain, resilient tile, carpet

Interior walls – masonry, metal stud/drywall, concrete

Wall finishes – ceramic, paint

Ceilings – acoustical, drywall, exposed