



Sacred Heart Catholic Church

Address: 321 S. Sawyer Street
Shawano, WI 54166

Project: Additions & Renovations

Description of work:

A two-story brick and concrete masonry unit project addition with full basement, renovation and extensive demolition. Construction consists of Vestibules and Gathering area, Elevator, Kitchenette, Toilet Rooms, Storage areas, two Carports and a full basement. The existing Nave area received a baptismal font as pictured above.

Demolition:

Cut and demo an opening thru the brick and concrete block sidewall of the Nave to create a new entry at Gathering Space. Cut and remove concrete basement walls at the new addition connection. Remove concrete/terrazzo stairs and landing making room for a three-stop elevator. Careful removal of stained glass windows for reuse in the new Gathering Space.

Basic Construction:

Building Addition -	11,175 sq. ft.
Building Renovation -	7,533 sq. ft.
Foundations -	concrete footings, concrete foundation walls and basement walls
Structural Steel -	framing at shored deck, lintels at openings, stair framing
Floors -	concrete slabs on grade, precast plank with concrete topping
Exterior Walls -	brick and block with 2" rigid insulation
Roof -	wood truss framing, light steel gauge trusses, steel joist and deck, asphalt shingles, single ply membrane roofing
Door and Frame -	aluminum entrances, hollow metal, solid wood doors, custom stile and rail wood doors
Windows -	aluminum, existing stained glass windows
Interior Walls -	metal stud and drywall, concrete block
Floor Covering -	carpeting, vinyl composition tile, ceramic tile
Finishes -	paint, ceramic tile, brick, wood and vinyl base
Ceilings -	acoustical ceilings, vinyl gypsum board tile, plaster and painted

Specialties:

laminated arches at Gathering Space, millwork at Gathering Space, Baptismal Font, casework