



Trinity Lutheran Church

Address: 709 W. Beckert Road
New London, WI

Project: Additions & Renovations

Project Cost: \$1 million

Building Construction:

Building Addition –	10,540 sq. ft.
Building Renovation –	12,000 sq. ft.
Foundations -	concrete footings and foundation walls
Floors –	concrete slab on grade, precast plank with 3” concrete topping
Exterior Walls –	2x6 wood framing, batt insulation, osb sheathing, dryvit system, brick veneer
Roof –	wood truss, roof sheathing, 15# felt, asphalt shingles
Interior Walls –	wood stud partitions, drywall panels textured and painted, concrete block units painted
Floor Covering –	carpet, vinyl composition tile, ceramic tile and rubber stair treads
Ceilings –	gypsum board textured and painted, vinyl gypsum board tile, acoustical panels
Doors and Frames –	aluminum entrances, hollow metal door and frames, solid wood doors and cased wood frames (interior)
Windows –	aluminum double hung and casement windows